

## 800 kW SOLAR SATURN MOBILE GENERATOR FLARE GAS PACKAGE





Year Of Packaging & Refurb	2022	
Engine Manufacture	TURBINE-X Energy Inc.	
Packaged By	TURBINE-X Energy Inc.	
Turbine Power Plant	Solar Saturn T1301	
Horsepower	1,300 HP	
Heat Rate (Approx.)	10,910 Btu/BHP-Hr	
Turbine Speed	22,300 RPM	
KW Output	750 kW Continuous (ISO)	
Generator	EM BEMAC II 800 kW 3PH 60Hz 1800 RPM 4,160 Volt (Transformer to 480V or 25kV Available)	
Reduction Gear Box	Solar Epicycle S10 1,800 RPM - Overhauled	
Fuel	Natural Gas – Sour fuel ready	
Control System	Motiv TCS	
Start System	Electric with battery bank	
Switchgear	Paralelling ready & grid connect ready	
Line Protection	Yes	
Condition	Turbine is overhauled, 0 hour. Package refurbished.	
Warranty	Yes	
FOB	Nisku, Alberta	
Purchase Price	Request pricing	
Monthly Rental	Request pricing	









Flat Rate LTSA (Long Term Service Agreement)	TBD USD per month based on natural gas operation 48 month LTSA, (a premium may be charged depending on sour gas level to increase overhaul frequency)	
LTSA Includes	Full warranty, 2 service visits per year, (blade wash & inspection). Turbine accessory drive and gearbox overhaul after 48 months. Emergency repairs deemed warrantable. Oil, oil filters and air filters required for change every 18 months.	
LTSA Excludes	Emergency repairs deemed not warrantable due to equipment neglect or miss use. Travel, accommodation and subsistence for servicing visits or emergency repair visits.	
	Extra servicing visits, repairs required or early overhaul due to consumption of sour gas.	

Note: LTSA (Long term service agreement) is required for leasing and rental contracts.

Note:Llease rates may fluctuate based on the credit review for each client.

Note: Minimum rental period is 12 months.

Note: Prices are plus GST, freight, set-up, start-up, commissioning, installation etc.





Overhauled, 0 Hour Solar T1401 Gas Turbine

**Control System Inferface** 

## **EXPECTED EMISSIONS**

ISO_NOX	47.1	PPMV
100_11071	17.1	
NOX	61.3	PPMV Corrected
		to 15% O2
СО	46.3	PPMV Corrected
		to 15% 02
нс	2.1	PPMV Corrected
		to 15% O2
02	16.78	%
CO2	2.41	%

Note: These numbers are average at ISO conditions on pipeline grade natural gas. Actuals may vary.

TURBINE-X ENERGY INC. PAGE 2 OF 3



For more information, please contact us at: +1 (780) 770-8885 or <a href="mailto:sales@turbine-x.com">sales@turbine-x.com</a>
Or visit our website at: x-group.com

TURBINE-X ENERGY INC. PAGE 3 OF 3